

Change Order #1 For Annex Cameras and WAPs

CUSTOMER

CITY OF LAUDERHILL

Doug Downs
5581 West Oakland Park Boulevard , Lauderhill,
FL 33313

Alpha Security & Fire Alarm Services, Inc.

5405 NW 102 Ave.
#229
Sunrise, FL 33351

Installation of Conduit and 9 cameras plus 4 WAPs.

Scope of Work:

This change order covers the addition of new cameras and wireless access points (WAPs) as per the updated project requirements. The cameras in the gym will need to be piped with 3/4" conduit.

Gym Cameras:

1. **5.0C-H5M-DO1-IR, 5MP Outdoor IR Dome Cameras(used indoors):**
 - Quantity: 3

Outside Gym Cameras:

2. **15C-H5A-3MH, 3x5MP, 270 Degree Multi-Lens Dome Cameras:**
 - Quantity: 2
 - **IRPTZ-MNT-WALL1 Wall Arm Mount for 270 Degree Cameras:**
 - Quantity: 2

Walkway outside Cameras:

3. **5.0C-H5M-DO1-IR, 5MP Outdoor IR Dome Cameras:**
 - Quantity: 3

Conduit and Mounts:

- 1. CNCVR-1001 Adapter 3/4 inch conduit for 6.1" dome camera 5-pack:
 - Quantity: 2 packs

Cat6 Cables for WAP Drops:





- 1. Cat6 Cable Installation:
 - Quantity: 4 drops for WAPs and 9 for Cameras











Conduit Installation (3/4" Conduit) for Gym Cameras:

- 1. 3/4 in. EMT Conduit:
 - Length: 300 feet
- 2. Pull 1900 Boxes (every 50 feet):
 - Quantity: 6 boxes

Lift Rental:

- 1. 19-Foot Lift Rental

| Items | Qty |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
|  Avigilon 15C-H5A-3MH H5A Multisensor 15MP Camera Module 3.3-5.7mm | x2 |
|  Avigilon CRNMT-1001 CORNER MNT FOR LRGE PENDT WLMT-1001 | x2 |
|  Avigilon H5AMH-AD-PEND1 Outdoor pendant mount adapter | x2 |
|  Avigilon IRPTZ-MNT-WALL1 Wall Arm for H4 IRPTZ or H4 Multisensor | x2 |

| Items | | Qty |
|-------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|-------|
|  | Avigilon 6.0C-H5A-DP1-IR 6MP H5A Outdoor Pendant IR Dome Camera with 4.9-8mm Lens | x6 |
|  | Avigilon CM-MT-WALL1 Pendant Wall Arm | x3 |
|  | Avigilon H6SL-MT-NPTA1 NPT Adapter for H6SL Dome Cameras | x3 |
|  | Avigilon 10.0C-H5DH-DO1-IR 2x 5MP H5A Dual Head Outdoor Camera | x1 |
|  | Avigilon H5DH-DO-JBOX1 Junction Box for H5A Dual Head Camera | x1 |
|  | Custom Cat6-Blue Custom Installation Network Cable Per Foot | x1000 |
|  | Hubbell RACO 2083 RACO 3/4" EMT 1 HOLE STRAP | x100 |
|  | Hubbell RACO 2003 EMT Set Screw Connector; 3/4 In.; Steel; Zinc Electroplated; Concrete Tight | x10 |
|  | Hubbell RACO 2023 EMT Set Screw Coupling; 3/4 In.; Steel; Zinc Electroplated; Concrete Tight | x1 |
|  | PVC Cond & Fits EMT-3/4 EMT Conduit-Straight; 3/4 In. 10 Ft. | x30 |

Items

Qty



ABC Lift Rental
Lift Rental

x1



Labor Project Management



Labor LABOR

Installation of Conduit and 9 cameras plus 4 WAPs. Total : \$29,223.08

Financial Summary

| | |
|-----------------------|--------------------|
| Subtotal | \$29,223.08 |
| Proposal Total | \$29,223.08 |

Payment Schedule

PAYMENT SCHEDULE

Payment 1 **Outstanding Proposal Balance • \$29,223.08** Due Upon Proposal Acceptance

Project Terms

Project Terms:

The estimated timeline for completion of the project is provided as a good faith estimate, but is subject to change based on the complexity of the work and the availability of resources. The client will be notified of any significant changes to the timeline.

The client is responsible for providing all necessary content, materials, and information required for the project in a timely manner. Delay in the receipt of necessary materials may result in delays in the project timeline.

The client is responsible for reviewing and approving all deliverables in a timely manner. Delay in review and approval may result in delays in the project timeline.

The client is responsible for providing final approval of the project before it is considered complete. Once the project is approved and finalized, no further changes can be made without additional fees.

Any issues or defects discovered after final approval will be addressed as a separate project, with additional fees as applicable.

The client retains ownership of all materials provided for the project, but grants the company the right to use the completed work for promotional purposes.

The company retains the right to terminate the project at any time, with a pro-rata refund of any payments made.

Additional Terms and Conditions:

In accepting this proposal, the customer agrees to the terms and conditions contained herein, including any attachments or riders with additional terms and conditions.

The terms and conditions of this agreement shall prevail over any variation in terms and conditions on any purchase order or other document issued by the customer.

Any changes to the system requested by the customer after the execution of this agreement shall be paid for by the customer and must be authorized in writing.

This proposal will be void if not accepted in writing within thirty (30) days from the date of the proposal.