



City of Lauderhill

City Commission
Chambers at City Hall
5581 W. Oakland Park
Blvd.
Lauderhill, FL, 33313
www.lauderhill-fl.gov

File Details

File Number: 24R-5875

File ID: 24R-5875

Type: Resolution

Status: Agenda Ready

Version: 1

Reference:

In Control: City Commission Meeting

*** Requester:** Kennie Hobbs

File Created: 09/10/2024

File Name: FIRE STATION 57

Final Action:

Title: RESOLUTION NO. 24R-09-217: A RESOLUTION AWARDING THE BID TO SUPREME BUILDER GROUP (RFP 2024-038) TO PROVIDE FIRE STATION 57 IMPROVEMENTS; AUTHORIZING THE CITY MANAGER TO EXECUTE ANY DOCUMENTS NECESSARY TO GIVE EFFECT TO THIS RESOLUTION; PROVIDING FOR PAYMENT IN AN AMOUNT NOT TO EXCEED \$569,189.00 UTILIZING FEMA HAZARD MITIGATION GRANT FUNDING FROM THE APPROPRIATE BUDGET CODE NUMBER; PROVIDING FOR AN EFFECTIVE DATE (REQUESTED BY CITY MANAGER, DESORAE GILES-SMITH).

Notes:

Agenda Date: 09/12/2024

Sponsors:

Enactment Date:

Attachments: RES-24R-09-217-BID-Supreme Builder Firestation 57-FEMA Grant Funds.pdf, RANKING, SUPEREME COST

Enactment Number:

Contact:

Hearing Date:

*** Drafter:** kwhite@lauderhill-fl.gov

Effective Date:

History of Legislative File

Ver- sion:	Acting Body:	Date:	Action:	Sent To:	Due Date:	Return Date:	Result:
---------------	--------------	-------	---------	----------	-----------	-----------------	---------

Text of Legislative File 24R-5875

Request Action:

APPROVE AWARD OF RFP TO FIRE STATION 57 IMPROVEMENTS

Need Summary Explanation/ Background:

AWARD THE RFP TO SUPREME BUILDER GROUP IN RESPONSE TO RFP 2024-038 REGARDING FIRE STATION 57 IMPROVEMENTS. FEMA HAZARD MITIGATION GRANT WAS AWARDED WHICH WILL BE USED FOR PAYMENT. PROPOSAL IS NOT TO EXCEED

\$569,189.00

Scope of work summarized as follows:

Concrete Flat Roof (3 Story building)

- Take off existing roof down to workable surface and haul away and dispose all debris from roof top.
- Supply and apply asphaltic primer.
- Supply and install tapered 1/4" polyIso insulation mopped with hot asphalt to concrete deck.
- Supply and install one ply of GAF strata vent loose laid.
- Supply and install one ply of Ruberoid 20 mopped with hot asphalt.
- Supply and install final layer of mineral cap sheet mopped with hot asphalt.
- Supply and install lead stack to plumbing vent pipes.
- Supply and install 1x6 wood blocking on perimeter edge.
- Supply and install galvanized steel drip edge, terminator bar and stucco stopper.
- Supply and install one ply of GAF strata vent loose laid.
- Supply and install one ply of Ruberoid 20 mopped with hot asphalt.
- Supply and install final layer of mineral cap sheet mopped with hot asphalt.
- Supply and install final layer of Ruberoid cap sheet mopped with hot asphalt in parapets.
- Supply and install lead stack to plumbing vent pipes.
- Supply and install roof rain drains and covers
- Supply and install 1x6 wood blocking on perimeter edge.
- Supply and install galvanized steel terminator bar and stucco stopper terminator bar and stucco stopper.

Cost Summary/ Fiscal Impact:

Grant funding in the amount not exceed \$569,189

Attachments:

1. final ranking
2. Supreme cost Proposal